


PIRANHA OFFROAD PRODUCTS P/N BTP150D2.8

'Piranha Off Road products are not associated in any way with Toyota Australia or any of its related companies'

To Suit TOYOTA PRADO
2.8Lt TDI 08/2015 May Not suit some Kakadu Models

PART NUMBER	BT150D2.8
APPROX FITTING TIME	1 Hour
MAX BATTERY SIZE	300mm L
MAX BATT WEIGHT	23Kg
CYCLE DUTY	Non AGM
TRAY LOCATION	DSF



PARTS INCLUDED WITH TRAY	
1 X Tray	
1 X Special top mount	
2 X J Bolt (1 X extra long)	
1 X XBTBP Backing Plate	
3 X M6 Wizlock Nuts	
4 X M6 Bolts 15mm	
1 X M6 Bolt 30mm	
1 X M6 X 26mm diam body Washer	
1 X M6 Nut	
RECOMMENDED ISOLATOR	
DBE140S or DBE180-SX	

1. Remove OE bolts from earth plate in inner guard and A/C support bracket, near tray area.
2. Remove plastic electrical cable mount, inner skirt below A/C pipe.
3. Remove front half of inner wheel arch guard liner and remove indicated OE bolt and install the supplied M6 X30mm long bolt from inside inner guard partially into engine bay. Fig 3
4. Fit tray in position with lower arm over thread now sticking out through inner guard.
5. Bolt tray in, put earth plate over tray arm. Fig 2
6. Now drill two 6mm holes through tray bracket into wheel arch with support plate under guard secure with 2XM6 15mm bolts and nuts. Fig 4
7. Remove the M6 X 30mm bolt from inside the inner guard, refit inner guard liner, replace M6X30mm bolt with body washer and tighten. Fig 3
8. Use M6 nut to secure lower tray arm to protruding thread against inner guard in engine bay.
9. Fit special top mount and using M6 bolt and nut, secure to front radiator support panel. Use longer "J" bolt to attach to vehicle mounting point located in front of air box. Fig 1